

COMMERCIAL PROPERTY – DRAINAGE REHABILITATION



Loading Area



Installation of Double Catch Basins at Loading Dock



New Concrete Pad and Asphalt Pavement



New Concrete Pad and Asphalt Pavement

Scope: Design, Specification/Tender, Contract Administration, Quality Observations

Services Provided: The site has drainage issues at the loading dock area. The water ponds in front of the loading door. New double Catch Basin at the loading dock was installed connected with another Catch Basin to allow the storm water flow. The loading dock was designed for 200 mm concrete pad using CSA 32MPa (C-2) concrete including M15 rebar@250mm c/c both direction.

Construction Value: \$508,000.00